


Six Steps to Success with Custom LSI



AMI






This custom circuit contains over 18,000 transistors



AMI's European Technical Center in Swindon, England



Custom circuits are packaged to the customer's needs

AMI's Six Step Program for Success in Custom LSI

If you're considering large scale integration (LSI) in the design of your product, the custom approach may be the most cost effective way to go.

Despite all the hoopla, microprocessors will not solve all your problems. Far from it, as many a manufacturer has found. For many high volume applications, a custom circuit is the most cost effective solution available—it's minimum size, minimum power and highest reliability because it's a minimum chip (often one chip) solution, tailored to your needs.

AMI has a world-wide custom LSI capability.

If the custom MOS/LSI approach seems appropriate for your particular product, and more and more customers are finding this so, you should talk to AMI, because we are acknowledged world leader in custom MOS/LSI. We're the only major high volume semiconductor company committed to the custom MOS/LSI business.

We're also the only custom circuit company with design and technology centers world wide—in Europe (at Swindon, England) and the U.S. (at Santa Clara, California and Pocatello, Idaho). Manufacturing operations are located in Santa Clara and Pocatello, while circuit assembly is done at AMI's subsidiary Korean Microsystems, Inc. (KMI) in Seoul, Korea.

No other company can match AMI's track record in developing state-of-the-art custom MOS products. With more than 1,200 custom devices designed and manufactured since 1967, AMI has more experience than any other integrated circuit company in building a wide variety of custom microcircuits.

AMI not only has the experience but the design engineering organization and the advanced production and testing facilities to produce the highest quality MOS/LSI circuits. Because AMI also offers standard memory, microprocessor, telecommunication and consumer products and the widest variety of custom LSI processes in the industry, we're able to be objective in helping customers determine their most cost effective approach.

AMI can participate at any level of the custom LSI process.

We're capable of participating at any level in the design of the


custom IC, from the classic "we'll design-and-produce-it-for-you" approach where we have complete responsibility, to the "Customer Tooling" cooperative approach for customers who do their own design but want us to do the manufacturing. We will even enter into long-term, fully-funded joint development agreements, designing ICs for families of products, joining together your systems designers with our circuit designers.

Since 1967, AMI has been providing customers with circuits that have enhanced the marketability of their products by adding features, increasing reliability and reducing space requirements and, finally, total systems cost.

We've developed a six step program in which you, the customer, can work with us to successfully develop the custom IC for your product by:

1. Considering All the Factors.
2. Looking At the Custom Options.
3. Selecting the Right MOS/LSI Process.
4. Designing The Best Circuit.
5. Fabricating the Optimum Device.
6. Testing For Reliable Performance.

The results are a unique product designed to your complete satisfaction.



Successful custom assignments flourish as cooperative enterprises

STEP TWO: Looking at the Custom Options.

There are two basic ways AMI teams up with its customers, although we are very flexible:

- AMI designs and makes the circuit to meet customer requirements; or,
- the customer designs the IC with AMI assistance and AMI produces it.

The total AMI approach

AMI's custom capability encompasses the entire development sequence of a product. The services we provide start with five conceptual planning steps:

- System Definition;
- System Design and Partitioning;
- Preliminary Logic Design/Simulation;
- Final Logic Design; and
- LSI Circuit Design.

First, system definition requires the customer to have full knowledge of the system requirements for the custom IC. Working

with AMI's application engineers, the two companies form a team to develop a final system which not only meets the needs, but optimizes performance and economics.

Second, system partitioning follows the joint development of system definition. This involves the cataloging of functions into MOS subfunctions, and then into chip functions. At this step the optimum MOS process for the application is chosen. Usually, functional flow charts and timing diagrams are generated at this time as a preliminary step in logic design.

Once partitioning is complete, preliminary logic design and simulation can be done. The chip functions are translated into MOS logic diagrams. Traditional breadboarding techniques are quite often used to verify these logic designs. AMI uses proprietary computerized simulation programs for verification. These programs check the design as well as help reduce time and cost factors for design verification.

Final logic design is next. First, system errors discovered through breadboarding or simulation are corrected. Earlier partitioning may be refined if the final logic design indicates the need. During the final logic design step all system design objectives are analyzed again. MOS logic diagrams are finalized, the chip sizes are estimated, and testing procedures are generated.


And then — the chip design. The topological chip layout is a precise science. The exact dimensions and placement for each transistor and other components must be determined. Here again AMI uses computerized circuit analysis programs to validate chip designs and verify that the design meets the performance objectives. The computerized analysis not only substantiates logic, it is an integral part of the on-going quality assurance program at AMI.

The cooperative approach

In this approach, the customer designs the circuit and has complete control over the logic and electrical requirements, the design budget and schedule, and the design changes prior to tooling.

Design workshops, consultation and information documentation packages are provided by us depending on the needs of the customer. We divide our customer interfacing into four phases: Phase 1 is a feasibility study; Phase 2 is a preliminary wafer fabrication or sample run; Phase 3, pre-production yield evaluation; and Phase 4, production.

Phase 1 begins before MOS logic is drawn. AMI customer tooling engineers provide suggestions on MOS design, discuss process and design rule parameters, provide a standard device, help plan ahead for testing, and provide information



Design span for the development of a typical custom circuit

on packaging and tooling interface.

Our experience has shown that the customer tooling interface works best when the customer is aware from the start of how we will make the device. If it's already been designed, Phase 1 begins when AMI provides a process and design rule questionnaire. This gives us information about packaging requirements, testing needs and tooling interface level. Our customer tooling experts review the data to see if AMI can meet all the requirements. At the end we supply at no charge a program plan, a firm quotation for the next two phases, and a budgetary quote for production.

During Phase 2 we'll process one wafer lot and then map, optically inspect, package and ship sample quantities of untested ICs, and, if the customer requires them, several untested wafers. Furthermore, AMI guarantees these samples will be within the agreed parameters and will meet our standards of quality and workmanship. The customer can supply working plates for Phase 2, or AMI will accept pattern generator tapes or 10x reticles.

After the customer approves the Phase 2 sample devices, AMI moves to Phase 3: pre-production yield evaluation. Here we guarantee the required manufacturing documentation, run acceptances on the test program, and build the wafer probe cards and the program board for AMI testers. We then make several

reproducibility runs of wafers and sort them for yield information.

From these runs AMI engineers will assemble and final test a number of good devices. The unit cost for them will be based on the costs of assembly, type of package and final test. These units provide the customer with a low volume production run for additional evaluation and start-up production commitments.

Pre-production deliveries actually start during Phase 3. Initial production deliveries during Phase 4 usually begin 9 to 11 weeks after approval of the pre-production units.

... But there are other options.

The custom LSI business is not an either/or sort of situation, and AMI, if nothing else, is flexible in the way we deal with our customers. The two previously described approaches are the most common ways customers themselves prefer to work with us. But AMI can interface with customers in many other ways.

For example, under certain low risk circumstances we will accept business which combines customer tooling Phases 2 and 3—prototyping and yield evaluation—prior to Phase 4 production. And for selected customers we enter into long term joint development agreements developing ICs for specific families of end products, becoming, in essence, the partner company's LSI research

and development group and production arm.

We're not biased particularly in favor of custom LSI, especially if it becomes clear it's not the best way to solve a customer problem. AMI is also a major microprocessor supplier in the 4-, 8-, and 16-bit categories: our own family of S2000 single chip microcomputers, the Motorola-designed 6800, and Texas Instrument's 9900 product line, respectively.

By having available both custom LSI and standard microprocessors, we can offer customers alternatives that can also combine the two. For example, to test the market for a new product, we can design a microprocessor-based system which provides a relatively quick, though not necessarily cost effective way to get a product to market. As part of the approach, we customize the microprocessor program or "software," and then, if the product is successful, design and make a custom LSI circuit dedicated to that particular application.

But if a microprocessor—ours or anyone else's—is the best solution, custom LSI is still useful, for microprocessors can't operate alone. They need interface devices. To achieve a system with a minimum chip count, custom devices can be designed to allow the customer to efficiently interface standard microprocessors with the customer's system.



AMI interactive graphics system eliminates digitizing, allows designers to check and alter circuit design directly on computer

STEP FOUR: Designing the best Circuit.

A key to AMI's success in the custom LSI business is its computer-aided design and layout capability. Our automated facilities are the most advanced in the semiconductor business, with a wealth of experience in supporting custom work. CAD software and hardware aids are employed at many points in the custom IC development cycle, from the early logic stage to making of the production tooling.

Logic simulation

Early in the design phase a set of computer programs is used to assure that the logic is sound. Via this simulator, the circuit's logic is modeled, exercised, and logic patterns determined for use later in test program generation. Designated the "TIDES Logic Simulator," it's especially written for MOS and contains logical functions and MOS transistors. Gate level logic simulation includes OR, AND, NOR, NAND, INVR, ROMs, shift registers, and several types of MOS transfer gates. It also includes such features as:

- multi-phase clocking schemes;
- free format input data;
- one logic element per statement;
- Boolean expressions and macros;
- user-oriented input pattern generation;
- versatile simulation and output formatting;
- convenient editing commands;
- simulation restart capability;
- input files partitioned into

constant and changeable portions; and,


- translation of the simulation results into test patterns.

Circuit simulation


At the circuit design and topological layout phase several computer models are used to identify any potential problems, such as undesirable circuit interactions. Exactly how the circuit behaves is modeled and the results used to assure the circuit will operate with in allowable tolerances.

The ASPEC circuit simulation process allows analysis of non-linear DC, non-linear transfer functions, non-linear transients and small signal (linear) AC. Built-in component models include independent voltage and current sources; linear elements such as resistance, inductance, capacitance, transconductance, voltage controlled switches, battery and coupled inductance; and non-linear elements such as junction field effect transistors and MOS-FETs.


The MOS-FET modeling program allows simulation of linear and saturation region DC operation; body effect as a result of substrate bias; channel length modulation in saturation; mobility reduction at elevated gate voltages; channel pinchoff; short channel effects; weak inversion; as well as full non-linear voltage-dependent modeling of the MOS capacitors used to model transient behavior.



Circuit architecture



Topological layout



Symbolic layout (SLIC)

Symbolic layout of ICs (SLIC)

AMI has developed an advanced method of symbolic layout of MOS ICs (SLIC) that results in a reduction in the total design cycle as much as 30 to 50 percent, with half the manpower effort and at half the cost of hand-drawn approaches. The system minimizes hand-drafting by using symbols that represent complex multi-level circuit architecture. For example, an "X" stands for a transistor (see diagram in upper right), "—" for a diffusion mask, "1" for a metal mask, "O" for a contact mask, and a "+" for a metal/diffusion crossover. And as the number of masks, and therefore, the complexity of the process increases, so does the number of symbols.

The SLIC circuit layout is drawn on mylar or gridded paper in accordance with two simple rules. First, if symbols are on adjacent grids then the topologies they represent are assumed to be connected. If not, they're not connected and their separation meets or exceeds minimum mask layouts. The designer must still draw by hand, but only symbols, a much faster process than drawing the topologies. Moreover, with SLIC, the designer gets a much better feel for how the circuit is developing.

To make sure the design rules are met for the particular MOS process to be used, we have developed a sophisticated array of checking aids, including:

- SDRC, or SLIC Design Rule Checking, which checks for all symbol-to-symbol layout rule violations;
- TRACE, which traces out the symbolic layout and locates shorts between named signal lines;
- CONTINUITY, which generates a net list from the logic simulation deck and compares it to a net list from the symbolic layout and prints out any differences it finds;
- DRC, or Design Rule Checking, a set of graphical routines for manipulating and checking mask geometrical information and design rule violations. It is used for circuits not drawn and checked with SLIC.

As a result, error correction, circuit modification and area relocations take only minutes at a remote terminal connected to the control computer. This contrasts with the days for either the traditional CAD or hand-drawn approaches. The next step in time saving is currently being installed. It consists of Computer-vision interactive graphic terminal systems which permit on-line generation and editing of composite drawings.

AMI does not use so-called "computer-designed," or standard cell circuits. Our circuits are laid out by experienced designers for minimum chip size. The computer is used only as an aid. In the traditional CAD approach a computer designs a circuit by

shuffling through a library of 200 or so standard structures. The custom chips that result are usually about twice as large as those done by hand. With SLIC, custom chips are often no larger than those drawn by hand, sometimes even smaller, and at no times more than three to five percent larger.

Moreover, SLIC and the other hardware and software design aids used by AMI are process independent and can be used interchangeably with any of our processes.

HARDWARE DESIGN AIDS

- On-site Burroughs 7760 computer with multiprocessing capability.
- Computer terminals (remote job-entry and dial in, located in Santa Clara, Calif., Pocatello, Idaho, and Swindon, England) built around a Prime computer, engineering design facilities which tie in to the on-site 7760 and time-sharing services.
- Two Computervision interactive graphics systems which provide on-line generation and editing of composite drawings; includes 3 drafting surfaces and 4 CRT displays.
- 1 Calma graphics system.
- High speed, high resolution Electromask 9 track pattern generator.
- Calma GDS-II high speed electrostatic plotter.
- Calcomp 748 Flatbed Plotter.

SOFTWARE DESIGN AIDS

- Aspec Circuit Simulator
- MOSFET Model Features
- Tides Logic Simulator
 - Logic Validation
 - Pattern Validation
 - Test Word Generation
- Symbolic Layout of ICs (SLIC)
- Geometrical Design Rule Checking (DRC)
- Trace and Continuity Checking



STEP FIVE: Fabricating the Optimum Device.

A partnership

AMI's long history of success in the custom MOS/LSI business (see chart upper right) is the result of a close, working partnership between AMI and each of our customers.

These customers have taken advantage of orders of magnitude increases in circuit complexity over the years, thereby reducing even further the component count in their systems.

The flexibility of AMI's development program allows the customer to select the interface point which is best suited to his particular needs. The most common interface points are noted as (*) in the review of the sequence of steps involved in developing a custom MOS/LSI circuit below:

1. System Definition/Design (*)

AMI and the customer work as a team to define system parameters. This teamwork assures that the final system definition will meet the customer's requirements and use MOS to best advantage for economy and performance. This includes selecting the MOS/LSI process which best fits the application. Flow charts and timing diagrams are often generated to detail system operation.

2. Preliminary logic design and simulation (*)

Designated chip functions are then translated into a detailed MOS/LSI logic diagram. A breadboard and/or AMI's proprietary logic simulation programs are used to verify this preliminary logic design.

3. Final logic design and system design review


Finalization of the logic design begins by correcting any errors found during the breadboard and simulation phase. At this point the system design objectives are carefully reviewed by the customer/AMI team, the logic diagrams are finalized, chip sizes are estimated and a test word sequence is generated. Electrical specifications are also finalized in anticipation of chip circuit design.



Custom circuit replaces breadboard: 1,000 components, 2,000 feet of wire



Digitizing enters circuit design elements into the computer



Silicon wafers are baked in 1,000°C diffusion oven to help form transistors

4. Chip circuit design

In designing the topological layout of the chip, the exact size of each transistor on the final logic diagram is determined. Computerized circuit analysis techniques are used to validate the chip circuit design, verifying that it meets all of the performance objectives.

5. Topological design

The first consideration in developing the topology or "surface geography" of the integrated circuit is the design of custom MOS/LSI circuit elements or "transistors." AMI does not rely on a library of standard MOS cells. Usually, each circuit element is hand-tailored to minimize the silicon area required. With a digitizing plotter, the circuit elements are woven into a multi-level composite plot and a careful design check is again made.

6. Artwork generation (*)

At AMI, MOS/LSI artwork is predominately created by a pattern generator. Operating under computer control, this system produces a very precise reticle plate which is ten times the size of the final device. The pattern generator eliminates the cutting, stripping and first reduction steps and related problems that are commonly associated with rubylith artwork. In addition, it provides a much higher precision and tolerances.

7. Mask fabrication (*)

The 10x reticle plate is then photoreduced to the actual size of the device, and this image is duplicated anywhere from 50 to 1,000 times (depending on the chip size) onto a tooling plate. This master plate is used for creating the photomasks used for actual wafer processing.

8. Wafer fabrication and map test

After each photomask image is transferred onto photo-sensitized 3 inch wafers of silicon, a series of chemical processes impart to the wafer the properties necessary to form transistors and diffused interconnections. Fabrication is completed by depositing an aluminum layer, etching this layer to form interconnections, and then depositing a passivating glass layer. The wafer is then map tested to insure that the basic process parameters have been satisfied.

9. Wafer sort test (*)

The wafer is now electrically probed to determine which chips meet certain functional requirements. As probe testing is performed, the circuits that do not function properly are inked for future identification and separation from properly functioning circuits.

10. Packaging


The tested wafer is scribed, then broken into individual chips and 100% optically inspected. Each functionally good die is mounted in its final package. The input and output pads on the chip are connected to the lead frame with either aluminum or gold wire, followed by a 100% preseat optical inspection. The die attach cavity is flushed with dry gas and a lid is hermetically attached over the chip compartment, or the lead frame and die are totally encapsulated in plastic.

11. Final test and characterization

Packaging prototypes are now subjected to rigorous parametric and functional tests to fully validate performance per the customer's requirements.

12. Product assurance tests


AMI holds an unmatched reliability record for MOS/LSI devices because of the frequent design and manufacturing checks made throughout the custom development cycle. These frequent checks culminate when the final package is subjected to visual, electrical and dimensional tests.



Datotek's Key Generator for secure communications offers 10^{52} combinations from one CMOS chip



Burroughs B-80 terminal makes good use of five custom LSI circuits



National Rejectors Industries' "Thinking" coin changer uses two LSI chips

AMI's worldwide facilities: Swindon, England Design Center

In addition to AMI's custom design facility in Santa Clara, California, we maintain a European technical center in Swindon, England to bring engineering technical expertise to European customers. The staff provides full custom circuit design support or will work with customers at any stage who have designed their own circuits. There is continual and close cooperation between the Swindon and Santa Clara engineering groups.

Computer-aided design support parallels that offered at the Santa Clara facility. The same type of logic and circuit simulator is used and converted to Swindon's Prime 400 computer. Upon completion of a design, a data base tape is transferred to Santa Clara for creation of 10x refiles on the AMI Electromask Pattern Generator.

AMI has three major facilities worldwide. Headquarters in Santa Clara has 327,000 square feet of manufacturing and office space and about 1,000 employees. Administration, R&D, the majority of the engineering staff, one of the company's two wafer fabrication facilities, pilot assembly and a final test facility are located there.

The other major fabrication facility is at Pocatello, Idaho, with 103,000 square feet and

about 600 employees. The plant includes some engineering, four fabricating lines and some final test activity.

Sales Offices

Western Area

100 East Wardlow Rd., Suite 203
Long Beach, California 90807
Tel: (213) 595-4768
TWX: 910-341-7668

3800 Homestead Road
Santa Clara, California 95051
Tel: (408) 249-4550
TWX: 910-338-0018

20709 N.E. 232nd Avenue
Battleground, Washington 98604
Tel: (206) 687-3101

Central Area

500 Higgins Road, Suite 210
Elk Grove Village, Illinois 60007
Tel: (312) 437-6496
TWX: 910-222-2853

Suite Number 204
408 South 9th Street
Noblesville, Indiana 46060
Tel: (317) 773-6330

29200 Vassar Ave., Suite 303
Livonia, Michigan 48152
Tel: (313) 478-9339
TWX: 810-242-2903

England

AMI Microsystems, Ltd.
108 A Commercial Road
Swindon, Wiltshire
Tel: (793) 31345 or 25445
TLX: 851-449349

France

AMI Microsystems, S.A.R.L.
124 Avenue de Paris
94300 Vincennes, France
Tel: (01) 374 00 90
TLX: 842-670500

Holland

AMI Microsystems, Ltd.
Calandstraat 62
Rotterdam, Holland
Tel: 010-36 14 83
TLX: 844-27402

DOMESTIC

725 So. Central Expressway, Suite A-9
Richardson, Texas 75080
Tel: (214) 231-5721
(214) 231-5285
TWX: 910-867-4766

Eastern Area

237 Whooping Loop
Altamonte Springs, Florida 32701
Tel: (305) 830-8889
TWX: 810-853-0269

1420 Providence Turnpike, Suite 220
Norwood, Massachusetts 02062
Tel: (617) 762-0726
TWX: 710-336-0073

20 Robert Pitt Drive, Room 212
Monsey, New York 10952
Tel: (914) 352-5333
TWX: 710-577-2827

Axe Wood East
Butler & Skippack Pikes, Suite 230
Ambler Pennsylvania 19002
Tel: (215) 643-0217
TWX: 510-661-3878

INTERNATIONAL

Italy

AMI Microsystems, S.p.A.
Via Pascoli 60
20133 Milano
Tel: 29 37 45 or 2360154
TLX: 843 32644

Japan

AMI Japan Ltd.
502 Nikko Sanno Building
2-5-3, Akasaka
Minato-ku, Tokyo 107
Tel: Tokyo 586-8131
TLX: 781-242-2180 AMI J

West Germany

AMI Microsystems, GmbH
Rosenheimer Strasse 30/32, Suite 237
8000 Munich 80, West Germany
Tel: (89) 483081
TLX: 841-522743
Rapifax: (89) 486591

To receive
you, please

Name _____

Company _____

Street _____

City _____

To receive

☐ Please

☐ Please

32 ☐ Connectors, Multi Pin Circular
33 ☐ Connectors, Printed Circuit
34 ☐ Connectors, Rad & Panel
35 ☐ Connectors, AD & DA
36 ☐ Cores, Magnet

70 ☐ Modems
71 ☐ Motors, Fractional H.P.
72 ☐ Multimeters

104 ☐ RF Instrumentation
105 ☐ Semiconductor Rectifiers
106 ☐ Servo Synchros & Resolvers
107 ☐ Shielding Materials

139 ☐ Voltmeters, Digital
140 ☐ Voltmeters, VTVM & VM
141 ☐ Voltmeters, AC & DC
142 ☐ Wire, Cable, Harness & Lacing



offers you, through TIDS, the latest technical information on its products, check only those categories which interest you, and which are listed in the return postcard below.

The TIDS system brings you only the product information you need from AMI and other manufacturers. You will not be deluged with unwanted material or

Here's the way the system works: In addition to the AMI product categories listed in blue, there are over 150 other categories listed below in black. Check only those products you are really interested in. TIDS will forward to you free, as it becomes available from various manufacturers, technical information of any sort that relates only to the categories you have selectively checked.

If you'd like to take advantage of the TIDS system, also complete the black section of the return card, and we will forward it to TIDS. You will shortly begin receiving the most current information published pertinent to your interests.

ALTHOUGH YOU MAY ALREADY BE A MEMBER OF THE TIDS SYSTEM, PLEASE COMPLETE THIS CARD TO MAKE SURE THAT ONLY YOUR CURRENT INTERESTS ARE REPRESENTED. EVEN IF YOU DO NOT WISH TO RECEIVE OTHER MANUFACTURER'S INFORMATION, MAKE SURE THAT YOU COMPLETE THE BLUE PORTION OF THE CARD AND RETURN IT TO AMI. WE WILL BE DISTRIBUTING ALL OF OUR LITERATURE ONLY THROUGH TIDS.



THE PRINCIPLE END PRODUCT OR SERVICE PROVIDED BY YOUR COMPANY:

1. INDUSTRIAL/COMMERCIAL	3. CONSUMER	5. R&D LABORATORY	7. YOUR PRINCIPAL JOB FUNCTION
1. Industrial Controls	1. Home & Portable Entertainment, Games	<input type="checkbox"/>	1. General or Non-Engineering Management
2. Power Distribution Equipment	2. Automotive/Airplane/Aviation		2. Engineering Management
3. Instr. Controls for Transportation Vehicles	3. Musical Instruments		3. Design Engineering (Circuits, Systems)
4. Instr. Controls for Lighting & Signs	4. Home & Portable Appliances and Tools		4. Reliability, Q.A., Test Engineer
5. Test & Measuring Equipment	5. Toy, Hobby and Kit		5. Manufacturing/Production
6. Test & Measuring Equipment	6. Watches, Clocks, Timekeeping		6. R&D
7. Telecommunications Equipment	7. Other		7. Purchasing/Procurement
8. Medical/Scientific Equipment			8. Marketing
9. Timers			9. Sales Rep or Distributor
10. Other			10. Other
2. COMPUTER/BUSINESS MACHINES	4. GOVERNMENT/MILITARY/AEROSPACE		NUMBER OF EMPLOYEES AT YOUR COMPANY
1. Large Computer (Mainframe)	1. Central Processor Units		<input type="checkbox"/> 1-9
2. Mini-Computer	2. Computer Peripheral		<input type="checkbox"/> 10-99
3. Peripheral Equipment	3. Instr. Test and Control		<input type="checkbox"/> 100-499
4. Office and Commercial Machines	4. Communication, Navigation, Guidance		<input type="checkbox"/> 500-999
5. Other	5. Ordnance, Weapons Systems		<input type="checkbox"/> Over 1000

I am interested in New Product Information on the following:

243 <input type="checkbox"/> MOS Custom	247 <input type="checkbox"/> MOS Clock and Timing Circuits	250 <input type="checkbox"/> Remote Control Circuits	292 <input type="checkbox"/> MOS Low End Single Chip μ P's
245 <input type="checkbox"/> ROMs, EPROMs	248 <input type="checkbox"/> MOS Organ Circuits	290 <input type="checkbox"/> MOS General Purpose μ P's	294 <input type="checkbox"/> MOS Telecom Circuits
246 <input type="checkbox"/> MOS RAMs	249 <input type="checkbox"/> Microprocessor Development Hardware	291 <input type="checkbox"/> MOS High Performance μ P's	295 <input type="checkbox"/> TouchControl (Capacitance) Switching

To receive new product information from other manufacturers, select carefully from the following:

1. Adhesives	37. Counters, Electronic	73. Optical Equipment	108. Silicones	252. Backplanes
2. Amplifiers, Audio	38. Crystal Oscillators	74. Optoelectronic Devices	109. Solder & Soldering Irons	253. Boards, Panel
3. Amplifiers, D.C.	39. Delay Lines	75. Oscillators	110. Solenoids	254. Converters, Code
4. Amplifiers, Differential	40. Diodes	76. Oscilloscopes	111. Spectrum Analyzers	255. Converters, Syn/Dig.
5. Amplifiers, High Frequency	41. Diodes, Zener & Reference	77. Photoelectric Devices	112. Switches, Illuminated	256. Diodes, Light Emitting
6. Amplifiers, Instruments & Controls	42. Encapsulating & Potting Compds	78. Plugs & Jacks	113. Switches, Miniature	257. Fiber Optics & Assys
7. Amplifiers, Operational	43. Encoders	79. Potentiometers	114. Switches, Push Button	258. Generators, Function
8. Amplifiers, RF	44. Fans & Blowers	80. Power Meters, RF	115. Switches, Rotary	259. IC's Thick Film
9. Amplifiers, RF	45. Fasteners	81. Power Supplies, Constant Current	116. Switches, Stepping	260. IC's Thin Film
10. Amplifiers, RF	46. Filters, Crystal	82. Power Supplies, High Current	117. Switches, Toggle	261. IC's Packaging
11. Amplifiers, RF	47. Filters, Electronic	83. Power Supplies, High Voltage	118. Temperature Equipment	262. Lasers
12. Amplifiers, RF	48. Filters, Electronic	84. Power Supplies, Lab Voltage	119. Temperature Control Devices	263. Packaging, Helix
13. Amplifiers, RF	49. Filters, Electronic	85. Power Supplies, Modular	120. Terminals & Jugs	264. Power Precision
14. Cable, Coaxial	50. Capacitors, Pkcs	86. Power Supplies, Modular	121. Test Equipment, Environmental	265. Power Supplies, Programmable
15. Cable, Flat	51. Capacitors, Surface	87. Power Supplies, Surface	122. Test Equipment, Environmental	266. Power Supplies, Solid State
16. Capacitors, Fixed	52. Capacitors, Variable	88. Power Supplies, Surface	123. Test Equipment, Environmental	267. Relays, Solid State
17. Capacitors, Variable	53. Calculators, Electronic Desk Top	89. Power Supplies, Surface	124. Test Equipment, Environmental	268. Relays, Solid State
18. Chemicals, Electronic Desk Top	54. Chemicals, Solvents	90. Power Supplies, Surface	125. Test Equipment, Environmental	269. Relays, Solid State
19. Chips, Active	55. ICs, Hybrid	91. Power Supplies, Surface	126. Test Equipment, Environmental	270. Relays, Solid State
20. Chips, Passive	56. ICs, Monolithic Linear Bipolar	92. Power Supplies, Surface	127. Test Equipment, Environmental	271. Relays, Solid State
21. Circuit Modules, Linear	57. ICs, Monolithic Linear Bipolar	93. Power Supplies, Surface	128. Test Equipment, Environmental	272. Relays, Solid State
22. Circuit Modules, Linear	58. ICs, Monolithic Linear Bipolar	94. Power Supplies, Surface	129. Test Equipment, Environmental	273. Relays, Solid State
23. Coils, RF & IF	59. ICs, Monolithic Linear Bipolar	95. Power Supplies, Surface	130. Test Equipment, Environmental	274. Relays, Solid State
24. Coils, Toroidal	60. Inductors, Indicator & Panel	96. Power Supplies, Surface	131. Test Equipment, Environmental	275. Relays, Solid State
25. Comm. Equip., Microwave	61. Inductors, Indicator & Panel	97. Power Supplies, Surface	132. Test Equipment, Environmental	276. Relays, Solid State
26. Communications Equipment, RF	62. Inductors, Indicator & Panel	98. Power Supplies, Surface	133. Test Equipment, Environmental	277. Relays, Solid State
27. Computers, Analog	63. Inductors, Indicator & Panel	99. Power Supplies, Surface	134. Test Equipment, Environmental	278. Relays, Solid State
28. Computers Digital (Med. & Lab)	64. Inductors, Indicator & Panel	100. Power Supplies, Surface	135. Test Equipment, Environmental	279. Relays, Solid State
29. Computers Digital (Miniature)	65. Inductors, Indicator & Panel	101. Power Supplies, Surface	136. Test Equipment, Environmental	280. Relays, Solid State
30. Connectors, Coaxial	66. Inductors, Indicator & Panel	102. Power Supplies, Surface	137. Test Equipment, Environmental	281. Relays, Solid State
31. Connectors, Min. & Submin.	67. Inductors, Indicator & Panel	103. Power Supplies, Surface	138. Test Equipment, Environmental	282. Relays, Solid State
32. Connectors, Multi Pin Circular	68. Inductors, Indicator & Panel	104. Power Supplies, Surface	139. Test Equipment, Environmental	283. Relays, Solid State
33. Connectors, Printed Circuit	69. Inductors, Indicator & Panel	105. Power Supplies, Surface	140. Test Equipment, Environmental	284. Relays, Solid State
34. Connectors, Rack & Panel	70. Inductors, Indicator & Panel	106. Power Supplies, Surface	141. Test Equipment, Environmental	285. Relays, Solid State
35. Converters, A/D & D/A	71. Inductors, Indicator & Panel	107. Power Supplies, Surface	142. Test Equipment, Environmental	286. Relays, Solid State
36. Cores, Magnet	72. Inductors, Indicator & Panel	108. Power Supplies, Surface	143. Test Equipment, Environmental	287. Relays, Solid State



BUSINESS REPLY MAIL


FIRST CLASS PERMIT NO. 472 SANTA CLARA, CA.

POSTAGE WILL BE PAID BY ADDRESSEE

AMERICAN MICROSYSTEMS, INC.
3800 Homestead Road
Santa Clara, California 95051



NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES



ATTENTION: MARKETING ADMINISTRATION



The background of the entire page is a detailed, high-resolution image of a microcircuit board. It features a complex network of red and blue conductive traces, pads, and vias. A large, rectangular area in the center-left is covered by a dense, fine-grained grid of red lines, likely representing a bond wire array or a specific functional block. The overall pattern is intricate and technical, typical of semiconductor packaging.

AMI

American Microsystems, Inc.

3800 Homestead Road, Santa Clara, California 95051